

Belden Brick Company

Project No. 0601-11 PTP

Six types of clay pavers were submitted to AMT Laboratories by PROSOCO, Inc. with a request to determine if application of the products evaluated will produce any surface alteration during new construction cleaning operations.

New Construction Cleaning was performed to evaluate the effectiveness of the selected PROSOCO products at removing excess Type S Mortar, and related new construction soiling, while limiting potential surface alterations to the decorative finish.

The attached report provides information about the PROSOCO products tested and descriptions of the test methods. The report includes test results as well as conclusions and recommendations. Recommendations are also provided in the chart below.

Recommendations

Sample	New Construction Cleaning Type S Mortar (14 Day Cleaning)
"4 x 8 Pawnee"	Sure Klean [®] Vana Trol [®] (1:6) OR (1:8)
"Landmark Gray Chamfer A"	Sure Klean [®] Vana Trol [®] (1:6) OR (1:8)
"Mod Belcrest 100 A	Sure Klean [®] Vana Trol [®] (1:6) OR (1:8)
" "Mod Belcrest 700 A"	Sure Klean [®] Vana Trol [®] (1:6) OR (1:8)
"Regimental Red Chamfer A"	Sure Klean [®] Vana Trol [®] (1:6) OR (1:8)
"Wheatfield Chamfer A"	Sure Klean [®] Vana Trol [®] (1:6) OR (1:8)

Apply all products in accordance with the manufacturer's recommendations provided on container labels and product data sheets. On-site testing should be conducted to determine the most appropriate cleaning, water repellent, or stain repellent products and procedures for a particular project. See product literature for additional application and safety information.